



# REPORT

3933 US ROUTE 11 CORTLAND, NEW YORK 13045

Order No. 100554696

Date: November 29, 2011

**REPORT NO. 100554696CRT-001e**

**TEST OF A FAISAL JASSIM TRADING CO  
CENTRAL AIR TERMINAL, SHUT OFF, SINGLE DUCT  
MODEL PITU 30 WITH ATTENUATOR, SIZE 12**

**RENDERED TO:**

**FAISAL JASSIM TRADING CO LLC  
PO BOX 1871  
DUBAI  
UNITED ARAB EMIRATES**

<u>Section No. *</u>	<u>Title of Test</u>
7	Primary Airflow Rate, cfm
7	Radiated Sound Power Level, dB
7	Discharge Sound Power Level, dB

The results contained herein are for technical evaluation only and are applicable only to the specific specimens referenced herein.

The tests herein reported have not been performed at the request of the Air Conditioning, Heating and Refrigeration Institute (AHRI), and use of these findings in any advertising or other literature shall state therein that the test is not part of the AHRI Certification Program.

\*AHRI Standard 880-2008

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to copy or distribute this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program. Measurement uncertainty budgets have been determined for applicable test methods and are available upon request.



**GENERAL**

Authorization to test the sample came from signed quote number 500338996. The sample was selected and supplied by the client and was received at the laboratories on November 8, 2011. The sample appeared to be in new, unused condition upon arrival.

**TEST METHOD**

The laboratory method used in conducting this series of tests was in accordance with Industry Standards AHRI 880-2008, "Performance Rating of Air Terminals" and ASHRAE 130-2008, "Methods of Testing Air Terminal Units".

The reference sound source used for this test was a calibrated Bruel & Kjaer Type 4204, which conforms to the above standard. Airflow was measured employing a nozzle metering station and a Dwyer Inclined Manometer Model No. 424-5.

Equipment	Calibration Date	Due Date	S/N	Model	Brand	Asset
Microphone/Pre - DF	5/5/2011	5/5/2012	2381159	4942	Brüel and Kjør	E449
Pulse Analyzer	3/17/2011	3/17/2012	2519258	7539	Brüel and Kjør	E446
Reference Sound Source	7/28/2009	7/28/2012	2036621	4204	Brüel and Kjør	A230
Manometer Incline	3/21/2011	3/21/2012	-	424-5	Dwyer	F166
Manometer Incline	4/5/2011	4/5/2012	S39C	424-5	Dwyer	F167
Microphone Calibrator	3/17/2011	3/17/2012	2130586	4231	Brüel and Kjør	A227

All static pressures in this report have been corrected to standard conditions.

**TEST SPECIMEN**

The test specimen consisted of a Faisal Jassim Trading Co Central Air Terminal Shut Off, Single Duct Model PITU 30 with attenuator, size 12. The terminal measured 21 3/4 inches in length by 19 3/4 inches in width by 15 3/4 inches in height. The inlet measured 12 inches in diameter while the outlet measured 19 3/4 by 15 3/4 inches. The sheet metal thickness measured 0.037 inches. The terminal was lined with 1 inch thick matt faced insulation. The base terminal was tested and rated with a flowcross inlet sensor. The attenuator measured 19 3/4 inches wide by 15 3/4 inches high by 35 inches long.



**RESULTS OF TEST – Model PITU 30 WITH ATTENUATOR, SIZE 12**

Measurement of the minimum operating pressure at 100% of standard airflow.

<u>Rated Airflow</u>	<u>Measured</u>
1600 cfm	-0.01 in. H <sub>2</sub> O

For the Casing Radiated Sound Power Level Test, the terminal was mounted in accordance with paragraph 6.1.4.2 of AHRI Standard 880-2008 and Figure 12 of ASHRAE 130-2008.

<u>Octave Band Center Frequency Hertz</u>	<u>Radiated Sound Power Level Lw dB re 10<sup>-12</sup> Watt</u>
125	74
250	62
500	54
1000	43
2000	37
4000	35
Air Volume in cfm	1600
Operating Pressure in. H <sub>2</sub> O	1.5

For the Discharge Sound Power Level Test, the unit was mounted in accordance with paragraph 6.1.4.1 of AHRI Standard 880-2008 and Figure 8 of ASHRAE 130-2008.

<u>Octave Band Center Frequency Hertz</u>	<u>Discharge Sound Power Level Lw dB re 10<sup>-12</sup> Watt</u>
125	76
250	67
500	57
1000	50
2000	51
4000	49
Air Volume in cfm	1600
Operating Pressure in. H <sub>2</sub> O	1.5

\*Sound Power Level data denoted with an asterisk has reached ambient levels in the test room or is determined by instrument limitations. Actual levels are less than or equal to the levels indicated.




**CONCLUSION**


The test method employed for this test employed no pass fail criteria and therefore discretion is left up to the client.

Dates of Tests: November 21 through November 29, 2011

Report Approved by:

  
Brian Cyr  
Engineer  
Acoustical Testing

Report Reviewed By:

  
James R. Kline  
Engineer/Quality Supervisor  
Acoustical Testing

Attachments: None