



REPORT

3933 US ROUTE 11 CORTLAND, NEW YORK 13045

Order No. 100673528

Date: March 7, 2012

REPORT NO. 100673528CRT-001b

**TEST OF A FAISAL JASSIM TRADING CO
CENTRAL AIR TERMINAL, SHUT OFF,
SINGLE DUCT MODEL PITU 40, SIZE 16**

RENDERED TO:

**FAISAL JASSIM TRADING CO LLC
PO BOX 1871
DUBAI
UNITED ARAB EMIRATES**

<u>Section No. *</u>	<u>Title of Test</u>
7	Primary Airflow Rate, cfm
7	Radiated Sound Power Level, dB
7	Discharge Sound Power Level, dB

The results contained herein are for technical evaluation only and are applicable only to the specific specimens referenced herein.

The tests herein reported have not been performed at the request of the Air Conditioning, Heating and Refrigeration Institute (AHRI), and use of these findings in any advertising or other literature shall state therein that the test is not part of the AHRI Certification Program.

*AHRI Standard 880-2008

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to copy or distribute this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program. Measurement uncertainty budgets have been determined for applicable test methods and are available upon request.



GENERAL

Authorization to test the sample came from signed quote number 500356181. The sample was selected and supplied by the client and was received at the laboratories on February 15, 2012. The sample appeared to be in new, unused condition upon arrival.

TEST METHOD

The laboratory method used in conducting this series of tests was in accordance with Industry Standards AHRI 880-2008, "Performance Rating of Air Terminals" and ASHRAE 130-2008, "Methods of Testing Air Terminal Units".

The reference sound source used for this test was a calibrated Bruel & Kjaer Type 4204, which conforms to the above standard. Airflow was measured employing a nozzle metering station and a Dwyer Inclined Manometer Model No. 424-5.

Equipment	Calibration Date	Due Date	S/N	Model	Brand	Asset
Microphone/Pre - DF	5/5/2011	5/5/2012	2381159	4942	Brüel and Kjær	E449
Pulse Analyzer	3/17/2011	3/17/2012	2519258	7539	Brüel and Kjær	E446
Reference Sound Source	7/28/2009	7/28/2012	2036621	4204	Brüel and Kjær	A230
Manometer Incline	3/21/2011	3/21/2012	-	424-5	Dwyer	F166
Manometer Incline	4/5/2011	4/5/2012	S39C	424-5	Dwyer	F167
Microphone Calibrator	3/17/2011	3/17/2012	2130586	4231	Brüel and Kjær	A227

All static pressures in this report have been corrected to standard conditions.

TEST SPECIMEN

The test specimen consisted of a Faisal Jassim Trading Co. Central Air Terminal Shut Off, Single Duct Model PITU 40, Size 16. The terminal measured 25 ¾ inches in length by 23 ¾ inches in width by 20 inches in height. The inlet measured 16 inches in diameter while the outlet measured 22 by 18 inches. The sheet metal thickness measured 0.037 inches. The terminal was lined with ¾ inch thick fabric faced insulation. The base terminal was tested and rated without an inlet sensor.



RESULTS OF TEST – Model PITU 40, Size 16

Measurement of the minimum operating pressure at 100% of standard airflow.

<u>Rated Airflow</u>	<u>Measured</u>
2800 cfm	-0.03 in. H ₂ O

For the Casing Radiated Sound Power Level Test, the terminal was mounted in accordance with paragraph 6.1.4.2 of AHRI Standard 880-2008 and Figure 12 of ASHRAE 130-2008.

<u>Octave Band Center Frequency Hertz</u>	<u>Radiated Sound Power Level Lw dB re 10⁻¹² Watt</u>
125	71
250	64
500	54
1000	46
2000	42
4000	35
Air Volume in cfm	2800
Operating Pressure in. H ₂ O	1.5

For the Discharge Sound Power Level Test, the unit was mounted in accordance with paragraph 6.1.4.1 of AHRI Standard 880-2008 and Figure 8 of ASHRAE 130-2008.

<u>Octave Band Center Frequency Hertz</u>	<u>Discharge Sound Power Level Lw dB re 10⁻¹² Watt</u>
125	76
250	73
500	66
1000	58
2000	57
4000	54
Air Volume in cfm	2800
Operating Pressure in. H ₂ O	1.5

*Sound Power Level data denoted with an asterisk has reached ambient levels in the test room or is determined by instrument limitations. Actual levels are less than or equal to the levels indicated.



CONCLUSION

The test method employed for this test employed no pass fail criteria and therefore discretion is left up to the client.

Dates of Tests: March 2 – 5, 2012

Report Approved by:

A handwritten signature in cursive script that reads "Brian Cyr".

Brian Cyr
Engineer
Acoustical Testing

Report Reviewed By:

A handwritten signature in cursive script that reads "James R. Kline".

James R. Kline
Engineer/Quality Supervisor
Acoustical Testing

Attachments: None